



SUMMARY TEST REPORT

FOR: Andersen Corporation
 100 Fourth Avenue North
 Bayport, MN 55003

Report Number: C2572.03-201-47
 Test End Date: 09/18/2012
 Report Date: 10/05/2012
 Test Record Retention End Date: 10/05/2016

SERIES TESTED: 400 Series Frenchwood Transom
 MODEL TESTED: FWT60110S IG

NAFS-08/-11 Class LC-PG65 Size Tested 71.3" x 21.9" DP+65/65
NAFS-05 N/A

<u>Test</u>	<u>Results Summary</u>
Operating Ease	N/A
Resistance to Air Infiltration	<0.01 cfm/ft ² (ASTM E283)
Resistance to Water Penetration	Pass at DP65 (ASTM E547)
Resistance to Structural Loading	Pass at DP65 (ASTM E330)
Forced Entry Resistance	Pass (ASTM F 588)

CAN/CSA A440-00, Evaluation to the prescriptive requirements were not performed

<u>Test</u>	<u>Rating</u>
Operating Ease	N/A
Air Tightness	Fixed
Water Tightness	B4
Wind Load Resistance	C4
Blow-Out	C4

<u>Test</u>	<u>Results Summary</u>
Impact	(N/A)
Pressure Cycling	(N/A)

REFERENCE: See ATI Report No. C2572.01-201-47 for complete test results.

A copy of this report will be retained by ATI for a period of four years. This report is the exclusive property of the client named herein and is applicable to the sample tested. Results obtained are tested values and do not constitute an opinion or endorsement by this laboratory.

ARCHITECTURAL TESTING, INC

ARCHITECTURAL TESTING, INC

Karl A. Lips-Eakins
 Senior Technician

Daniel A. Johnson
 Director - Regional Operations

849 Western Avenue North
 St. Paul, MN 55117
 Phone: 651-636-3835
 Fax: 717-764-4129
 www.archtest.com