

MIAMI-DADE COUNTY PERFORMANCE TEST REPORT

Report No.: B5634.01-201-18

Rendered to:

KML WINDOWS, INC. Strathroy, Ontario

PRODUCT TYPE: Aluminum Clad Wood Fixed Windows **SERIES/MODEL**: Coastal Aluminum Clad Direct Glazed Fixed Windows - HPIR and Mono

This report contains in its entirety:

Cover Page: 1 page Report Body: 54 pages Sketches: 4 pages Drawings: 24 pages

Test Dates: 12/16/11 **Through**: 02/16/12

Report Date: 02/24/12

Test Record Retention End Date: 02/16/22 **Miami-Dade County Notification No.**: ATIMN 11024

Report Date: 02/24/12

Test Report No.: B5634.01-201-18

Test Record Retention End Date: 02/16/22

Page 1 of 54

1.0 Report Issued To: KML Windows. Inc.

71 Second Street

Strathroy, Ontario, Canada N7G 3H8

2.0 Test Laboratory: Architectural Testing, Inc.

849 Western Avenue North

St. Paul. Minnesota 651-636-3835

3.0 Project Summary:

Architectural Testing

3.1 Product Type: Aluminum Clad Wood Fixed Windows

3.2 Series/Model: Coastal Aluminum Clad Direct Glazed Fixed Windows - HPIR and Mono

- **3.3 Compliance Statement**: Results obtained are tested values and were secured by using the designated test methods. The samples were tested per Florida Building Code, Test Protocols for High Velocity Hurricane Zone, Protocols TAS 201-94, TAS 202-94 and TAS 203-94. Samples #1, #2, #3 and #4 tested met the performance requirements set forth in the protocols for a +70.0 / -80.0 psf Design Pressure Samples #5, #6, #7, #8, #9 and #10 tested met the performance requirements set forth in the protocols for a ±70.0 psf *Design Pressure* rating.
- 3.4 Miami-Dade County Notification No.: ATIMN 11024
- **3.5 Test Dates**: 12/16/11 02/16/12
- **3.6 Test Location**: Architectural Testing, Inc. test facility in St. Paul, Minnesota.
- 3.7 Test Sample Source: The test specimens were provided by the client. Representative samples of the test specimens will be retained by Architectural Testing for a minimum of ten years from the test completion date.
- **3.8 Drawing Reference**: The test specimen drawings have been reviewed by Architectural Testing and are representative of the test specimens reported herein. Test specimen construction was verified by Architectural Testing per the drawings located in Appendix C. Any deviations are documented herein or on the drawings.

Company

3.9 List of Official Observers:

Name

Jeffrey P. Crandall	Architectural Testing, Inc.
Dax R. Stoehr	Architectural Testing, Inc.
Tony D. Gavin	Architectural Testing, Inc.
Shawn G. Collins, P.E.	Architectural Testing, Inc.
Eric J. Schoenthaler	Architectural Testing, Inc.



Report Date: 02/24/12 Test Record Retention End Date: 02/16/22

Page 2 of 54

4.0 Test Specifications:

Architectural Testing

TAS 201-94, Impact Test Procedures.

TAS 202-94, Criteria for Testing Impact and Non Impact Resistant Building Envelope Components Using Uniform Static Air Pressure Loading.

TAS 203-94, Criteria for Testing Products Subject to Cyclic Wind Pressure Loading.

5.0 Test Specimen #1 Description:

5.1 Product Type: Aluminum Clad Wood Rectangle Fixed Window

5.2 Series/Model: Coastal Aluminum Clad Direct Glazed Rectangle Window - HPIR

5.3 Product Sizes:

Overall Area : 50.0 ft ²	Width (inches)	Height (inches)
Overall size	60	120

5.4 Frame Construction:

Frame Member	Material	Description		
All	Aluminum / wood	Exterior aluminum cladding was secured onto interior pine wood frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.		

	Joinery Type	Detail
Aluminum cladding	Miter	Corners were miter cut, sealed with a gasket and secured with one #8 x 1" screw and one #8 x 2-1/2" screw per corner.
Wood	Miter	Corners were miter cut, sealed with a gasket and secured with two #8 x 2" screws per corner.

Architectural Testing

Test Report No.: B5634.01-201-18

Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 3 of 54

5.0 Test Specimen #1 Description: (Continued)

5.6 Glazing:

Glass Type	Spacer Type	Interior Lite	Exterior Lite	Glazing Method	
1" IG	Edgetech silicone foam spacer (1/4" x 1/2")	5.7 mm heat- strengthene d / 0.090 SentryGlas Plus by DuPont / 5.7 mm heat- strengthene d	6.0 mm Tempered	The glass was set from the interior against a Dow Corning 995 silicone back bedding and back filled. Wood glazing stops with 7/16" by 1/32" double-sided adhesive foam tape were secured with 1-1/4" brad nails 2" from each corner and spaced 6" on center.	

Location	Quantity	Daylight Opening	Glass Bite
Frame	1	57" x 117"	1/2"

5.7 Drainage: No drainage was utilized.

5.8 Hardware: No hardware was utilized.

5.9 Reinforcement: No reinforcement was utilized.

6.0 Installation:

Location	Anchor Description	Anchor Location
Frame	#12 x 2-1/2" screws	Through the frame 4" from each
perimeter	#12 x 2-1/2 Screws	corner and spaced 6" on center.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 4 of 54

7.0 Test Specimen #2 Description:

7.1 Product Type: Aluminum Clad Wood Fixed Springline Window

7.2 Series/Model: Coastal Aluminum Clad Direct Glazed Springline Window - HPIR

7.3 Product Sizes:

Overall Area : 47.4 ft ²	Width (inches)	Height (inches)
Overall size	60	120

7.4 Frame Construction:

Frame Member	Material	Description		
Jambs and sill	Aluminum / wood	Exterior aluminum cladding was secured onto interior pine wood frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.		
Head jamb	Aluminum / LVL	Exterior aluminum cladding was secured onto interior LVL frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.		

	Joinery Type	Detail
Aluminum cladding	Miter	Corners were miter cut, sealed with a gasket and secured with one #8 x 1" screw and one #8 x 2-1/2" screw per corner.
Upper wood	Butt	Corners were butted, sealed with wood glue and secured with three #8 x 2" screws per corner. The joint was additionally secured with a 24 gauge, 12" gusset plate secured with eight #8 x 3/4" screws.
		Corners were miter cut, sealed with a gasket and secured with two #8 x 2" screws per corner.



Test Record Retention End Date: 02/16/22

Page 5 of 54

7.0 Test Specimen #2 Description: (Continued)

7.6 Glazing:

Architectural Testing

Glass Type	Spacer Type	Interior Lite	Exterior Lite	Glazing Method	
1" IG	Edgetech silicone foam spacer (1/4" x 1/2")	5.7 mm heat- strengthene d / 0.090 SentryGlas Plus by DuPont / 5.7 mm heat- strengthene d	6.0 mm Tempered	The glass was set from the interior against a Dow Corning 995 silicone back bedding and back filled. Wood glazing stops with 7/16" by 1/32" double-sided adhesive foam tape were secured with 1-1/4" brad nails 2" from each corner and spaced 6" on center.	

Location	Quantity	Daylight Opening	Glass Bite
Frame	1	57" x 117"	1/2"

7.7 Drainage: No drainage was utilized.

7.8 Hardware: No hardware was utilized.

7.9 Reinforcement: No reinforcement was utilized.

8.0 Installation:

Location	Anchor Description	Anchor Location	
Frame perimeter	Installation clips	The clips were secured to the frame with three #8 x 3/4" screws. The clips were secured to the buck with one #8 x 1-5/8" screw. The clips were 4" from each corner and spaced 6" on center.	
Nail flange	11 gauge 1-1/2" hot galvanized roofing nails	The nails were 3" from each corner and spaced 10" on center.	



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 6 of 54

9.0 Test Specimen #3 Description:

9.1 Product Type: Aluminum Clad Wood Fixed Archtop Window

9.2 Series/Model: Coastal Aluminum Clad Direct Glazed Archtop Window - Mono

9.3 Product Sizes:

Overall Area : 49.3 ft ²	Width (inches)	Height (inches)
Overall size	60	120

9.4 Frame Construction:

Frame Member	Material	Description	
Jambs and sill	Aluminum / wood	Exterior aluminum cladding was secured onto interior pine wood frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.	
Head jamb	Aluminum / LVL	Exterior aluminum cladding was secured onto interior LVL frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.	

	Joinery Type	Detail
Aluminum cladding	Miter	Corners were miter cut, sealed with a gasket and secured with one #8 x 1" screw and one #8 x 2-1/2" screw per corner.
Wood	Miter	Corners were miter cut, sealed with a gasket and secured with two #8 x 2" screws per corner.

Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 7 of 54

9.0 Test Specimen #3 Description: (Continued)

9.6 Glazing:

Architectural Testing

Glass Type	Glazing	Glazing Method
Monolithic	5.7 mm heat- strengthened / 0.090 SentryGlas Plus by DuPont / 5.7 mm heat- strengthened	The glass was set from the interior against a Dow Corning 995 silicone back bedding and back filled. Wood glazing stops with 7/16" by 1/32" double-sided adhesive foam tape were secured with 1-1/4" brad nails 2" from each corner and spaced 6" on center.

Location	Quantity	Daylight Opening	Glass Bite
Frame	1	57" x 117"	1/2"

9.7 Drainage: No drainage was utilized.

9.8 Hardware: No hardware was utilized.

9.9 Reinforcement: No reinforcement was utilized.

10.0 Installation:

Location	Anchor Description	Anchor Location	
Frame	#12 x 2-1/2" screws	Through the frame 4" from each	
perimeter	#12 x 2-1/2 Screws	corner and spaced 6" on center.	



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 8 of 54

11.0 Test Specimen #4 Description:

11.1 Product Type: Aluminum Clad Wood Fixed Rectangle Window

11.2 Series/Model: Coastal Aluminum Clad Direct Glazed Rectangle Window - Mono

11.3 Product Sizes:

Overall Area : 50.0 ft ²	Width (inches)	Height (inches)
Overall size	60	120

11.4 Frame Construction:

Frame Member	Material	Description	
All	Aluminum / wood	Exterior aluminum cladding was secured onto interior pine wood frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.	

	Joinery Type	Detail
Aluminum cladding	Miter	Corners were miter cut, sealed with a gasket and secured with one #8 x 1" screw and one #8 x 2-1/2" screw per corner.
Wood	Miter	Corners were miter cut, sealed with a gasket and secured with two #8 x 2" screws per corner.



Test Record Retention End Date: 02/16/22

Page 9 of 54



11.0 Test Specimen #4 Description: (Continued)

11.6 Glazing:

Glass Type	Glazing	Glazing Method
Monolithic	5.7 mm heat- strengthened / 0.090 SentryGlas Plus by DuPont / 5.7 mm heat- strengthened	The glass was set from the interior against a Dow Corning 995 silicone back bedding and back filled. Wood glazing stops with 7/16" by 1/32" double-sided adhesive foam tape were secured with 1-1/4" brad nails 2" from each corner and spaced 6" on center.

Location	Quantity	Daylight Opening	Glass Bite
Frame	1	57" x 117"	1/2"

11.7 Drainage: No drainage was utilized.

11.8 Hardware: No hardware was utilized.

11.9 Reinforcement: No reinforcement was utilized.

12.0 Installation:

Location	Anchor Description	Anchor Location
Frame Installation clips		The clips were secured to the frame with three #8 x 3/4" screws. The clips were secured to the buck with one #8 x 1-5/8" screw. The clips were 4" from each corner and spaced 6" on center.
Nail flange	11 gauge 1-1/2" hot galvanized roofing nails	The nails were 3" from each corner and spaced 10" on center.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 10 of 54

13.0 Test Specimen #5 Description:

13.1 Product Type: Aluminum Clad Wood Fixed Rectangle Window

13.2 Series/Model: Coastal Aluminum Clad Direct Glazed Rectangle Window - HPIR


13.3 Product Sizes:

Overall Area : 36.0 ft ²	Width (inches)	Height (inches)
Overall size	54	96

13.4 Frame Construction:

Frame Member	Material	Description	
All	Aluminum / wood	Exterior aluminum cladding was secured onto interior pine wood frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.	

	Joinery Type	Detail
Aluminum cladding	Miter	Corners were miter cut, sealed with a gasket and secured with one #8 x 1" screw and one #8 x 2-1/2" screws per corner.
Wood	Miter	Corners were miter cut, sealed with a gasket and secured with two #8 x 2" screws per corner.



Test Record Retention End Date: 02/16/22

Page 11 of 54



13.0 Test Specimen #5 Description: (Continued)

13.6 Glazing:

Glass Type	Spacer Type	Interior Lite	Exterior Lite	Glazing Method	
1" IG	Edgetech silicone foam spacer (1/4" x 1/2")	5.7 mm annealed / 0.090 SentryGlas Plus by DuPont / 5.7 mm annealed	6.0 mm Tempered	The glass was set from the interior against a Dow Corning 995 silicone back bedding and back filled. Wood glazing stops with 7/16" by 1/32" double-sided adhesive foam tape were secured with 1-1/4" brad nails 2" from each corner and spaced 6" on center.	

Location	Quantity	Daylight Opening	Glass Bite
Frame	1	51" x 93"	1/2"

13.7 Drainage: No drainage was utilized.

13.8 Hardware: No hardware was utilized.

13.9 Reinforcement: No reinforcement was utilized.

14.0 Installation:

Location	Anchor Description	Anchor Location
Frame perimeter	Installation clips	The clips were secured to the frame with three #8 x 3/4" screws. The clips were secured to the buck with one #8 x 1-5/8" screw. The clips were 4" from each corner and spaced 6" on center.
Nail flange	11 gauge 1-1/2" hot galvanized roofing nails	The nails were 3" from each corner and spaced 10" on center.



Test Record Retention End Date: 02/16/22

Page 12 of 54

15.0 Test Specimen #6 Description:

15.1 Product Type: Aluminum Clad Wood Fixed Springline Window

15.2 Series/Model: Coastal Aluminum Clad Direct Glazed Springline Window - HPIR

15.3 Product Sizes:

Architectural Testing

Overall Area : 33.8 ft ²	Width (inches)	Height (inches)
Overall size	54	96

15.4 Frame Construction:

Frame Member	Material	Description	
Jambs and sill	Aluminum / wood	Exterior aluminum cladding was secured onto interior pine wood frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.	
Head jamb	Aluminum / LVL	Exterior aluminum cladding was secured onto interior LVL frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.	

	Joinery Type	Detail
Aluminum cladding	Miter	Corners were miter cut, sealed with a gasket and secured with one #8 x 1" screw and one #8 x 2-1/2" screw per corner.
Upper wood	Butt	Corners were butted, sealed with wood glue and secured with three #8 x 2" screws per corner. The joint was additionally secured with a 24 gauge, 12" gusset plate secured with eight #8 x 3/4" screws.
Lower wood	Miter	Corners were miter cut, sealed with a gasket and secured with two #8 x 2" screws per corner.

Architectural Testing

Test Report No.: B5634.01-201-18

Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 13 of 54

15.0 Test Specimen #6 Description: (Continued)

15.6 Glazing:

Glass Type	Spacer Type	Interior Lite	Exterior Lite	Glazing Method	
1" IG	Edgetech silicone foam spacer (1/4" x 1/2")	5.7 mm annealed / 0.090 SentryGlas Plus by DuPont / 5.7 mm annealed	6.0 mm Tempered	The glass was set from the interior against a Dow Corning 995 silicone back bedding and back filled. Wood glazing stops with 7/16" by 1/32" double-sided adhesive foam tape were secured with 1-1/4" brad nails 2" from each corner and spaced 6" on center.	

Location	Quantity	Daylight Opening	Glass Bite
Frame	1	51" x 93"	1/2"

15.7 Drainage: No drainage was utilized.

15.8 Hardware: No hardware was utilized.

15.9 Reinforcement: No reinforcement was utilized.

16.0 Installation:

Location	Anchor Description	Anchor Location
Frame	#12 x 2-1/2" screws	Through the frame 4" from each
perimeter	#12 x 2-1/2 Screws	corner and spaced 6" on center.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 14 of 54

17.0 Test Specimen #7 Description:

17.1 Product Type: Aluminum Clad Wood Fixed Archtop Window

17.2 Series/Model: Coastal Aluminum Clad Direct Glazed Archtop Window - Mono

17.3 Product Sizes:

Overall Area : 34.7 ft ²	Width (inches)	Height (inches)
Overall size	54	96

17.4 Frame Construction:

Frame Member	Material	Description	
	Aluminum / wood	Exterior aluminum cladding was secured onto	
Jambs and sill		interior pine wood frame members with	
		1/4" x 3/8" staples 7" from each end and	
		spaced 8" on center.	
		Exterior aluminum cladding was secured onto	
Head jamb	Aluminum / LVL	interior LVL frame members with 1/4" x 3/8"	
		staples 7" from each end and spaced 8" on	
		center.	

	Joinery Type	Detail
Aluminum cladding	Miter	Corners were miter cut, sealed with a gasket and secured with one #8 x 1" screw and one #8 x 2-1/2" screw per corner.
Wood	Miter	Corners were miter cut, sealed with a gasket and secured with two #8 x 2" screws per corner.

Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 15 of 54

17.0 Test Specimen #7 Description: (Continued)

17.6 Glazing:

Architectural Testing

Glass Type	Glazing	Glazing Method
Monolithic	5.7 mm heat- strengthened / 0.090 SentryGlas Plus by DuPont / 5.7 mm heat- strengthened	The glass was set from the interior against a Dow Corning 995 silicone back bedding and back filled. Wood glazing stops with 7/16" by 1/32" double-sided adhesive foam tape were secured with 1-1/4" brad nails 2" from each corner and spaced 6" on center.

Location	Quantity	Daylight Opening	Glass Bite
Frame	1	51" x 93"	1/2"

17.7 Drainage: No drainage was utilized.

17.8 Hardware: No hardware was utilized.

17.9 Reinforcement: No reinforcement was utilized.

18.0 Installation:

Location	Anchor Description	Anchor Location
Frame	#12 x 2-1/2" screws	Through the frame 4" from each
perimeter	#12 x 2-1/2 Screws	corner and spaced 6" on center.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 16 of 54

19.0 Test Specimen #8 Description:

19.1 Product Type: Aluminum Clad Wood Fixed Rectangle Window

19.2 Series/Model: Coastal Aluminum Clad Direct Glazed Rectangle Window - HPIR

19.3 Product Sizes:

Overall Area : 15.0 ft ²	Width (inches)	Height (inches)
Overall size	36	60

19.4 Frame Construction:

Frame Member	Material	Description		
All	Aluminum / wood	Exterior aluminum cladding was secured onto interior pine wood frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.		

	Joinery Type	Detail
Aluminum cladding	Miter	Corners were miter cut, sealed with a gasket and secured with one #8 x 1" screw and one #8 x 2-1/2" screw per corner.
Wood	Miter	Corners were miter cut, sealed with a gasket and secured with two #8 x 2" screws per corner.

Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 17 of 54

19.0 Test Specimen #8 Description: (Continued)

19.6 Glazing:

Architectural Testing

Glass Type	Spacer Type	Interior Lite	Exterior Lite	Glazing Method	
1" IG	Edgetech silicone foam spacer (1/4" x 1/2")	3.9 mm annealed / 0.090 PVB by DuPont / 3.9 mm annealed	3.0 mm annealed	The glass was set from the interior against a Dow Corning 995 silicone back bedding and back filled. Wood glazing stops with 7/16" by 1/32" double-sided adhesive foam tape were secured with 1-1/4" brad nails 2" from each corner and spaced 6" on center.	

Location	Quantity	Daylight Opening	Glass Bite
Frame	1	33" x 57"	1/2"

19.7 Drainage: No drainage was utilized.

19.8 Hardware: No hardware was utilized.

19.9 Reinforcement: No reinforcement was utilized.

20.0 Installation:

Location	Anchor Description Anchor Location		
Frame perimeter	#12 x 2-1/2" screws	Through the frame 4" from each corner and spaced 12" on center.	



Test Record Retention End Date: 02/16/22

Page 18 of 54

21.0 Test Specimen #9 Description:

21.1 Product Type: Aluminum Clad Wood Fixed Springline Window

21.2 Series/Model: Coastal Aluminum Clad Direct Glazed Springline Window - HPIR

21.3 Product Sizes:

Architectural Testing

Overall Area : 14.0 ft ²	Width (inches)	Height (inches)
Overall size	36	60

21.4 Frame Construction:

Frame Member	Material	Description
Jambs and sill	Aluminum / wood	Exterior aluminum cladding was secured onto interior pine wood frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.
Head jamb	Aluminum / LVL	Exterior aluminum cladding was secured onto interior LVL frame members with 1/4" x 3/8" staples 7" from each end and spaced 8" on center.

	Joinery Type	Detail
Aluminum cladding	Miter	Corners were miter cut, sealed with a gasket and secured with one #8 x 1" screw and one #8 x 2-1/2" screw per corner.
Upper wood	Butt	Corners were butted, sealed with wood glue and secured with three #8 x 2" screws per corner. The joint was additionally secured with a 24 gauge, 12" gusset plate secured with eight #8 x 3/4" screws.
Lower wood	Miter	Corners were miter cut, sealed with a gasket and secured with two #8 x 2" screws per corner.



Test Record Retention End Date: 02/16/22

Page 19 of 54



21.0 Test Specimen #9 Description: (Continued)

21.6 Glazing:

Glass Type	Spacer Type	Interior Lite	Exterior Lite	Glazing Method	
1" IG	Edgetech silicone foam spacer (1/4" x 1/2")	3.9 mm annealed / 0.090 PVB by DuPont / 3.9 mm annealed	3.0 mm annealed	The glass was set from the interior against a Dow Corning 995 silicone back bedding and back filled. Wood glazing stops with 7/16" by 1/32" double-sided adhesive foam tape were secured with 1-1/4" brad nails 2" from each corner and spaced 6" on center.	

Location	Quantity	Daylight Opening	Glass Bite
Frame	1	33" x 57"	1/2"

21.7 Drainage: No drainage was utilized.

21.8 Hardware: No hardware was utilized.

21.9 Reinforcement: No reinforcement was utilized.

22.0 Installation:

Location	Anchor Description	Anchor Location	
Frame perimeter	Installation clips	The clips were secured to the frame with three #8 x 3/4" screws. The clips were secured to the buck with one #8 x 1-5/8" screw. The clips were 4" from each corner and spaced 12" on center.	
Nail flange	11 gauge 1-1/2" hot galvanized roofing nails	The nails were 3" from each corner and spaced 10" on center.	



Architectural Testing

Test Report No.: B5634.01-201-18

Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 20 of 54

23.0 Test Specimen #10 Description:

23.1 Product Type: Aluminum Clad Wood Fixed Archtop Window

23.2 Series/Model: Coastal Aluminum Clad Direct Glazed Archtop Window - Mono


23.3 Product Sizes:

Overall Area : 14.6 ft ²	Width (inches)	Height (inches)
Overall size	36	60

23.4 Frame Construction:

Frame Member	Material	Description
	Aluminum / wood	Exterior aluminum cladding was secured onto
Jambs and sill		interior pine wood frame members with
		1/4" x 3/8" staples 7" from each end and
		spaced 8" on center.
		Exterior aluminum cladding was secured onto
Head jamb	Aluminum / LVL	interior LVL frame members with 1/4" x 3/8"
		staples 7" from each end and spaced 8" on
		center.

_	Joinery Type	Detail
Aluminum cladding	Miter	Corners were miter cut, sealed with a gasket and secured with one #8 x 1" screw and one #8 x 2-1/2" screws per corner.
Wood	Miter	Corners were miter cut, sealed with a gasket and secured with two #8 x 2" screws per corner.



Test Record Retention End Date: 02/16/22

Page 21 of 54

23.0 Test Specimen #10 Description: (Continued)

23.6 Glazing:

Architectural Testing

Glass Type	Glazing	Glazing Method
Monolithic	3.9 mm annealed / 0.090 PVB by DuPont / 3.9 mm annealed	The glass was set from the interior against a Dow Corning 995 silicone back bedding and back filled. Wood glazing stops with 7/16" by 1/32" double-sided adhesive foam tape were secured with 1-1/4" brad nails 2" from each corner and spaced 6" on center.

Location	Quantity	Daylight Opening	Glass Bite
Frame	1	33" x 57"	1/2"

23.7 Drainage: No drainage was utilized.

23.8 Hardware: No hardware was utilized.

23.9 Reinforcement: No reinforcement was utilized.

24.0 Installation:

Location	Anchor Description	Anchor Location
Frame perimeter	#12 x 2-1/2" screws	Through the frame 4" from each corner and spaced 12" on center.



Test Record Retention End Date: 02/16/22

Page 22 of 54

25.0 Test Specimen #1 Results: The temperature during testing was 74°F. The results are tabulated as follows:

Protocol TAS 202-94, Static Air Pressure Tests

Test Unit #1

Architectural Testing

Design Pressure: +70.0 / -80.0 psf

Title of Test	Results
Air Infiltration at 1.57 psf (25 mph)	<0.01 cfm/ft ²
Air Infiltration at 6.24 psf (50 mph)	<0.01 cfm/ft ²

	Indicator Reading (inches)		inches)
Structural Loads 50% of Test Pressure (+52.50 psf)	#1	#2	#3
Maximum Deflection	0.03	0.04	0.04
Permanent Set	0.01	0.01	0.01
Design Pressure (+70.00 psf)			
Maximum Deflection	0.04	0.05	0.04
Permanent Set	0.01	0.01	0.02
50% of Test Pressure (-60.00 psf)			
Maximum Deflection	0.07	0.07	0.06
Permanent Set	0.03	0.03	0.03
Design Pressure (-80.00 psf)			
Maximum Deflection	0.12	0.13	0.11
Permanent Set	0.06	0.05	0.05
Water Infiltration 15% Positive Design Pressure (+10.50 psf)		Pass	
Test Pressure (+105.00 psf)			
Maximum Deflection	0.05	0.06	0.05
Permanent Set	0.01	0.01	0.01
Test Pressure (-120.00 psf)			
Maximum Deflection	0.25	0.25	0.23
Permanent Set	0.09	0.08	0.08
Forced Entry - ASTM F 588-07		Pass	

Note: See Architectural Testing Sketch #1 for indicator locations.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 23 of 54

25.0 Test Specimen #1 Results: (Continued)

Protocol TAS 201-94, Impact Test Procedures

Missile Weight: 9.1 lbs **Missile Length**: 94"

Muzzle Distance from Test Specimen: 16'0"

Impact #1: Missile Velocity: 50.0 fps		
Impact Area:	Center of glazing	
Observations:	Missile hit target area; no rips, tears or penetrations	
Results:	Pass	

Impact #2: Missile Velocity: 50.1 fps		
Impact Area:	Upper left glazing corner	
Observations:	Missile hit target area; deglazed along entire corner	
Results:	Fail	



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 24 of 54

25.0 Test Specimen #1 (Retest) Results: (Continued)

Protocol TAS 201-94, Impact Test Procedures

Missile Weight: 9.1 lbs Missile Length: 96-1/2"

Muzzle Distance from Test Specimen: 16'0"

Impact #1: Missile Velocity: 50.4 fps		
Impact Area:	Center of glazing	
Observations:	Missile hit target area; no rips, tears or penetrations	
Results:	Pass	

Impact #2: Missile Velocity: 50.4 fps		
Impact Area:	Upper left glazing corner	
Observations:	Missile hit target area; no rips, tears or penetrations	
Results:	Pass	

Note: See Architectural Testing Sketch #1 for impact locations.



Test Record Retention End Date: 02/16/22

Page 25 of 54



25.0 Test Specimen #1 (Retest) Results: (Continued)

Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Unit #1 (Retest)

Design Pressure: +70.0 / -80.0 psf

POSITIVE PRESSURE

Pressure	Number of	Average Cycle Time	Maximum De	eflection at Indi	cator (inches)
Range (psf)	Cycles	(seconds)	#1	#2	#3
14.0 to 35.0	3500	2.61	0.01	0.01	0.01
0 to 42.0	300	2.72	0.08	0.07	0.07
35.0 to 56.0	600	1.81	0.11	0.10	0.10
21.0 to 70.0	100	2.75	0.13	0.13	0.12
	Permanent Set (inches)		hes)		
			0.03	0.03	0.03

NEGATIVE PRESSURE

_			I		-
Pressure	Number of	Average Cycle Time	Maximum De	eflection at Indi	cator (inches)
Range (psf)	Cycles	(seconds)	#1	#2	#3
24.0 to 80.0	50	2.84	0.10	0.09	0.07
40.0 to 64.0	1050	2.16	0.09	0.08	0.05
0 to 48.0	50	2.77	0.07	0.05	0.03
16.0 to 40.0	3350	1.90	0.06	0.05	0.02
Permanent Set (inches)		hes)			
			0.01	0.01	0.01

Observations: No additional damage or deglazing was observed.

Result: Pass

 ${\it Note:}\,\,{\it See}\,\,{\it Architectural}\,\,{\it Testing}\,\,{\it Sketch}\,\,\#1\,{\it for indicator locations.}$



Test Record Retention End Date: 02/16/22

Page 26 of 54



26.0 Test Specimen #2 Results: (Continued)

Protocol TAS 202-94, Static Air Pressure Tests

Test Unit #2

Design Pressure: +70.0 / -80.0 psf

Title of Test	Results
Air Infiltration at 1.57 psf (25 mph)	<0.01 cfm/ft ²
Air Infiltration at 6.24 psf (50 mph)	<0.01 cfm/ft ²

	Indicator Reading (inches)		nches)
Structural Loads 50% of Test Pressure (+52.50 psf)	#1	#2	#3
Maximum Deflection	0.09	0.09	0.08
Permanent Set	0.02	0.02	0.02
Design Pressure (+70.00 psf)			
Maximum Deflection	0.12	0.12	0.11
Permanent Set	0.03	0.02	0.02
50% of Test Pressure (-60.00 psf)			
Maximum Deflection	0.23	0.23	0.22
Permanent Set	0.06	0.06	0.06
Design Pressure (-80.00 psf)			
Maximum Deflection	0.33	0.32	0.31
Permanent Set	0.07	0.07	0.07
Water Infiltration 15% Positive Design Pressure (+10.50 psf) Pass			
Test Pressure (+105.00 psf)			
Maximum Deflection	0.18	0.18	0.17
Permanent Set	0.03	0.03	0.03
Test Pressure (-120.00 psf)			
Maximum Deflection	0.51	0.50	0.48
Permanent Set	0.07	0.06	0.07
Forced Entry - ASTM F 588-07		Pass	

Note: See Architectural Testing Sketch #1 for indicator locations.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 27 of 54

26.0 Test Specimen #2 Results: (Continued)

Protocol TAS 201-94, Impact Test Procedures

Missile Weight: 9.1 lbs **Missile Length**: 94"

Muzzle Distance from Test Specimen: 16'0"

Impact #1: Missile Velocity: 49.6 fps		
Impact Area:	Center of glazing	
Observations:	Missile hit target area; no rips, tears or penetrations	
Results:	Pass	

Impact #2: Missile Velocity: 50.0 fps	
Impact Area:	Upper left glazing corner
Observations:	Missile hit target area; no rips, tears or penetrations
Results:	Pass

Note: See Architectural Testing Sketch #1 for impact locations.





Page 28 of 54



26.0 Test Specimen #2 Results: (Continued)

Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Unit #2

Design Pressure: +70.0 / -80.0 psf

POSITIVE PRESSURE

Pressure	Number of	Average Cycle Time	Maximum De	eflection at Indi	cator (inches)
Range (psf)	Cycles	(seconds)	#1	#2	#3
14.0 to 35.0	3500	2.10	0.09	0.10	0.10
0 to 42.0	300	2.45	0.08	0.09	0.10
35.0 to 56.0	600	2.15	0.12	0.13	0.14
21.0 to 70.0	100	2.93	0.12	0.14	0.15
			Peri	nanent Set (inc	hes)
			0.05	0.04	0.05

NEGATIVE PRESSURE


		MEGITIT			
Pressure	Number of	Average Cycle Time	Maximum De	eflection at Indi	cator (inches)
Range (psf)	Cycles	(seconds)	#1	#2	#3
24.0 to 80.0	50	2.67	0.13	0.13	0.14
40.0 to 64.0	1050	1.90	0.12	0.12	0.13
0 to 48.0	50	2.44	0.11	0.10	0.11
16.0 to 40.0	3350	1.68	0.10	0.09	0.10
			Perr	nanent Set (inc	hes)
			0.06	0.06	0.06

Observations: No additional damage or deglazing was observed.

Result: Pass

 ${\it Note:}\,\,{\it See}\,\,{\it Architectural}\,\,{\it Testing}\,\,{\it Sketch}\,\,\#1\,{\it for indicator locations.}$





Page 29 of 54



27.0 Test Specimen #3 Results: (Continued)

Protocol TAS 202-94, Static Air Pressure Tests

Test Unit #3

Design Pressure: +70.0 / -80.0 psf

Title of Test	Results
Air Infiltration at 1.57 psf (25 mph)	<0.01 cfm/ft ²
Air Infiltration at 6.24 psf (50 mph)	<0.01 cfm/ft ²

	Indicator Reading (inches)		nches)
Structural Loads 50% of Test Pressure (+52.50 psf)	#1	#2	#3
Maximum Deflection	0.05	0.05	0.05
Permanent Set	0.02	0.01	0.01
Design Pressure (+70.00 psf)			
Maximum Deflection	0.09	0.09	0.08
Permanent Set	0.03	0.02	0.02
50% of Test Pressure (-60.00 psf)			
Maximum Deflection	0.15	0.15	0.14
Permanent Set	0.04	0.04	0.04
Design Pressure (-80.00 psf)			
Maximum Deflection	0.24	0.23	0.21
Permanent Set	0.05	0.05	0.05
Water Infiltration 15% Positive Design Pressure (+10.50 psf)		Pass	
Test Pressure (+105.00 psf)			
Maximum Deflection	0.18	0.18	0.15
Permanent Set	0.04	0.04	0.04
Test Pressure (-120.00 psf)			
Maximum Deflection	0.47	0.45	0.42
Permanent Set	0.04	0.04	0.05
Forced Entry - ASTM F 588-07		Pass	

Note: See Architectural Testing Sketch #1 for indicator locations.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 30 of 54

27.0 Test Specimen #3 Results: (Continued)

Protocol TAS 201-94, Impact Test Procedures

Missile Weight: 9.1 lbs **Missile Length**: 94"

Muzzle Distance from Test Specimen: 16'0"

Impact #1: Missile Velocity: 50.5 fps		
Impact Area:	Center of glazing	
Observations:	Missile hit target area; no rips, tears or penetrations	
Results:	Pass	

Impact #2: Missile Velocity: 50.1 fps	
Impact Area:	Upper left glazing corner
Observations:	Missile hit target area; no rips, tears or penetrations
Results:	Pass

Note: See Architectural Testing Sketch #1 for impact locations.





Page 31 of 54



27.0 Test Specimen #3 Results: (Continued)

Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Unit #3

Design Pressure: +70.0 / -80.0 psf

POSITIVE PRESSURE

Pressure	Number of	Average Cycle Time	Maximum De	eflection at Indi	cator (inches)
Range (psf)	Cycles	(seconds)	#1	#2	#3
14.0 to 35.0	3500	1.91	0.10	0.10	0.09
0 to 42.0	300	2.72	0.11	0.11	0.10
35.0 to 56.0	600	1.69	0.13	0.13	0.12
21.0 to 70.0	100	2.52	0.16	0.16	0.15
			Perr	nanent Set (inc	hes)
			0.08	0.08	0.08

NEGATIVE PRESSURE

Pressure	Number of	Average	Maximum De	flection at Indi	cator (inches)
Range (psf)	Cycles	Cycle Time (seconds)	#1	#2	#3
24.0 to 80.0	50	2.28	0.14	0.14	0.12
40.0 to 64.0	1050	2.09	0.13	0.13	0.12
0 to 48.0	50	2.65	0.09	0.09	0.07
16.0 to 40.0	3350	2.09	0.08	0.08	0.07
			Perr	nanent Set (inc	hes)
			0.05	0.05	0.04

Observations: No additional damage or deglazing was observed.

Result: Pass

Note: See Architectural Testing Sketch #1 for indicator locations. Test Specimens #3 and #4 were cycled in a common chamber.



Test Record Retention End Date: 02/16/22

Page 32 of 54



28.0 Test Specimen #4 Results: (Continued)

Protocol TAS 202-94, Static Air Pressure Tests

Test Unit #4

Design Pressure: +70.0 / -80.0 psf

Title of Test	Results
Air Infiltration at 1.57 psf (25 mph)	<0.01 cfm/ft ²
Air Infiltration at 6.24 psf (50 mph)	<0.01 cfm/ft ²

	Indicator Reading (inches)		nches)
Structural Loads 50% of Test Pressure (+52.50 psf)	#1	#2	#3
Maximum Deflection	0.06	0.05	0.04
Permanent Set	0.01	0.01	0.01
Design Pressure (+70.00 psf)			
Maximum Deflection	0.11	0.09	0.08
Permanent Set	0.03	0.02	0.02
50% of Test Pressure (-60.00 psf)			
Maximum Deflection	0.14	0.14	0.13
Permanent Set	0.05	0.05	0.05
Design Pressure (-80.00 psf)			
Maximum Deflection	0.23	0.22	0.21
Permanent Set	0.07	0.07	0.07
Water Infiltration 15% Positive Design Pressure (+10.50 psf)		Pass	
Test Pressure (+105.00 psf)			
Maximum Deflection	0.18	0.16	0.13
Permanent Set	0.05	0.04	0.03
Test Pressure (-120.00 psf)			
Maximum Deflection	0.42	0.39	0.37
Permanent Set	0.08	0.07	0.09
Forced Entry - ASTM F 588-07		Pass	

Note: See Architectural Testing Sketch #1 for indicator locations.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 33 of 54

28.0 Test Specimen #4 Results: (Continued)

Protocol TAS 201-94, Impact Test Procedures

Missile Weight: 9.1 lbs **Missile Length**: 94"

Muzzle Distance from Test Specimen: 16'0"

Impact #1: Missile Velocity: 49.1 fps		
Impact Area:	Center of glazing	
Observations:	Missile hit target area; no rips, tears or penetrations	
Results:	Pass	

Impact #2: Missile Velocity: 50.0 fps		
Impact Area: Lower left glazing corner		
Observations:	Missile hit target area; no rips, tears or penetrations	
Results:	Pass	

Note: See Architectural Testing Sketch #1 for impact locations.



Test Record Retention End Date: 02/16/22

Page 34 of 54



28.0 Test Specimen #4 Results: (Continued)

Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Unit #4

Design Pressure: +70.0 / -80.0 psf

POSITIVE PRESSURE

Pressure Range (psf) Number of Cycles	Number of	Average Cycle Time	Maximum Deflection at Indicator (inches)		
	(seconds)	#1	#2	#3	
14.0 to 35.0	3500	1.91	0.11	0.11	0.12
0 to 42.0	300	2.72	0.14	0.14	0.13
35.0 to 56.0	600	1.69	0.18	0.19	0.17
21.0 to 70.0	100	2.52	0.23	0.23	0.21
			Permanent Set (inches)		
			0.10	0.10	0.08

NEGATIVE PRESSURE

Pressure Range (psf) Number of Cycles	Number of	Average	Maximum Deflection at Indicator (inches)		
	Cycle Time (seconds)	#1	#2	#3	
24.0 to 80.0	50	2.28	0.21	0.22	0.21
40.0 to 64.0	1050	2.09	0.20	0.21	0.20
0 to 48.0	50	2.65	0.15	0.15	0.15
16.0 to 40.0	3350	2.09	0.14	0.14	0.14
			Permanent Set (inches)		
			0.06	0.04	0.05

Observations: No additional damage or deglazing was observed.

Result: Pass

Note: See Architectural Testing Sketch #1 for indicator locations. Test Specimens #3 and #4 were cycled in a common chamber.



Test Record Retention End Date: 02/16/22

Page 35 of 54

29.0 Test Specimen #5 Results: (Continued)

Protocol TAS 202-94, Static Air Pressure Tests

Test Unit #5

Architectural Testing

Design Pressure: ±70.00 psf

Title of Test	Results
Air Infiltration at 1.57 psf (25 mph)	<0.01 cfm/ft ²
Air Infiltration at 6.24 psf (50 mph)	<0.01 cfm/ft ²

	Indicator Reading (inches)		
Structural Loads 50% of Test Pressure (+52.50 psf)	#1	#2	#3
Maximum Deflection	0.05	0.05	0.04
Permanent Set	0.01	0.01	0.01
Design Pressure (+70.00 psf)			
Maximum Deflection	0.08	0.08	0.07
Permanent Set	0.02	0.02	0.02
50% of Test Pressure (-52.50 psf)			
Maximum Deflection	0.06	0.06	0.06
Permanent Set	0.01	0.01	0.02
Design Pressure (-70.00 psf)			
Maximum Deflection	0.10	0.10	0.09
Permanent Set	0.02	0.02	0.03
Water Infiltration 15% Positive Design Pressure (+10.50 psf)	Pass		
Test Pressure (+105.00 psf)			
Maximum Deflection	0.14	0.13	0.12
Permanent Set	0.04	0.03	0.03
Test Pressure (-105.00 psf)			
Maximum Deflection	0.18	0.18	0.17
Permanent Set	0.03	0.03	0.03
Forced Entry - ASTM F 588-07		Pass	

Note: See Architectural Testing Sketch #2 for indicator locations.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 36 of 54

29.0 Test Specimen #5 Results: (Continued)

Protocol TAS 201-94, Impact Test Procedures

Missile Weight: 9.1 lbs **Missile Length**: 94"

Muzzle Distance from Test Specimen: 16'0"

Impact #1: Missile Velocity: 49.8 fps				
Impact Area: Center of glazing				
Observations:	Missile hit target area; no rips, tears or penetrations			
Results:	Pass			

Impact #2: Missile Velocity: 49.5 fps			
Impact Area: Upper right glazing corner			
Observations:	Missile hit target area; no rips, tears or penetrations		
Results:	Pass		

Note: See Architectural Testing Sketch #2 for impact locations.



Report Date: 02/24/12 Test Record Retention End Date: 02/16/22

Page 37 of 54



29.0 Test Specimen #5 Results: (Continued)

Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Unit #5

Design Pressure: ±70.00 psf

POSITIVE PRESSURE

Pressure	Number of	Average Cycle Time (seconds)	Maximum Deflection at Indicator (inches)		
Range (psf)	Cycles		#1	#2	#3
14.0 to 35.0	3500	2.00	0.08	0.08	0.07
0 to 42.0	300	2.79	0.12	0.12	0.11
35.0 to 56.0	600	2.38	0.16	0.15	0.15
21.0 to 70.0	100	2.54	0.18	0.18	0.17
			Permanent Set (inches)		hes)
			0.06	0.06	0.05

NEGATIVE PRESSURE

NEGATIVET RESSURE					
Pressure Range	Number of	Average Cycle Time (seconds)	Maximum De	flection at Indi	cator (inches)
(psf)	Cycles		#1	#2	#3
21.0 to 70.0	50	2.79	0.16	0.15	0.15
35.0 to 56.0	1050	1.76	0.12	0.13	0.12
0 to 42.0	50	2.38	0.09	0.09	0.09
14.0 to 35.0	3350	1.73	0.08	0.09	0.08
			Permanent Set (inches)		hes)
			0.02	0.03	0.02

Observations: No additional damage or deglazing was observed.

Result: Pass

Note: See Architectural Testing Sketch #2 for indicator locations. Test Specimens #5 and #6 were cycled in a common chamber.



Test Record Retention End Date: 02/16/22

Page 38 of 54

30.0 Test Specimen #6 Results: (Continued)

Protocol TAS 202-94, Static Air Pressure Tests

Test Unit #6

Architectural Testing

Design Pressure: ±70.00 psf

Title of Test	Results
Air Infiltration at 1.57 psf (25 mph)	<0.01 cfm/ft ²
Air Infiltration at 6.24 psf (50 mph)	<0.01 cfm/ft ²

	Indicator Reading (inches)		
Structural Loads 50% of Test Pressure (+52.50 psf)	#1	#2	#3
Maximum Deflection	0.04	0.04	0.04
Permanent Set	0.01	0.01	0.01
Design Pressure (+70.00 psf)			
Maximum Deflection	0.06	0.06	0.06
Permanent Set	0.02	0.02	0.02
50% of Test Pressure (-52.50 psf)			
Maximum Deflection	0.05	0.05	0.05
Permanent Set	0.01	0.01	0.01
Design Pressure (-70.00 psf)			
Maximum Deflection	0.09 0.09 0.0		0.08
Permanent Set	0.01	0.01	0.01
Water Infiltration 15% Positive Design Pressure (+10.50 psf)		Pass	
Test Pressure (+105.00 psf)			
Maximum Deflection	0.08	0.08	0.06
Permanent Set	0.01	0.01	0.01
Test Pressure (-105.00 psf)			
Maximum Deflection	0.17	0.18	0.18
Permanent Set 0.03 0.03		0.04	
Forced Entry - ASTM F 588-07		Pass	

Note: See Architectural Testing Sketch #2 for indicator locations.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 39 of 54

30.0 Test Specimen #6 Results: (Continued)

Protocol TAS 201-94, Impact Test Procedures

Missile Weight: 9.1 lbs **Missile Length**: 94"

Muzzle Distance from Test Specimen: 16'0"

Impact #1: Missile Velocity: 50.1 fps				
Impact Area: Center of glazing				
Observations:	Missile hit target area; no rips, tears or penetrations			
Results:	Pass			

Impact #2: Missile Velocity: 49.8 fps				
Impact Area: Upper left glazing corner				
Observations:	Missile hit target area; no rips, tears or penetrations			
Results:	Pass			

Note: See Architectural Testing Sketch #2 for impact locations.



Report Date: 02/24/12 Test Record Retention End Date: 02/16/22

Page 40 of 54



30.0 Test Specimen #6 Results: (Continued)

Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Unit #6

Design Pressure: ±70.00 psf

POSITIVE PRESSURE

Pressure	Number of	Average Cycle Time (seconds)	Maximum De	eflection at Indi	cator (inches)
Range (psf)	Cycles		#1	#2	#3
14.0 to 35.0	3500	2.00	0.04	0.04	0.04
0 to 42.0	300	2.79	0.07	0.07	0.08
35.0 to 56.0	600	2.38	0.08	0.08	0.09
21.0 to 70.0	100	2.54	0.09	0.09	0.10
			Permanent Set (inches)		hes)
			0.03	0.03	0.03

NEGATIVE PRESSURE

NEGITIVET RESSORE					
Pressure Range Number	Number of	Average Cycle Time (seconds)	Maximum De	flection at Indi	cator (inches)
(psf)	Cycles		#1	#2	#3
21.0 to 70.0	50	2.79	0.07	0.07	0.08
35.0 to 56.0	1050	1.76	0.07	0.06	0.07
0 to 42.0	50	2.38	0.05	0.05	0.05
14.0 to 35.0	3350	1.73	0.04	0.04	0.04
			Permanent Set (inches)		hes)
			0.02	0.03	0.02

Observations: No additional damage or deglazing was observed.

Result: Pass

Note: See Architectural Testing Sketch #2 for indicator locations. Test Specimens #5 and #6 were cycled in a common chamber.



Test Record Retention End Date: 02/16/22

Page 41 of 54

31.0 Test Specimen #7 Results: (Continued)

Protocol TAS 202-94, Static Air Pressure Tests

Test Unit #7

Architectural Testing

Design Pressure: ±70.00 psf

Title of Test	Results
Air Infiltration at 1.57 psf (25 mph)	<0.01 cfm/ft ²
Air Infiltration at 6.24 psf (50 mph)	<0.01 cfm/ft ²

	Indicator Reading (inches)		
Structural Loads 50% of Test Pressure (+52.50 psf)	#1	#2	#3
Maximum Deflection	0.02	0.02	0.02
Permanent Set	0.01	0.01	0.01
Design Pressure (+70.00 psf)			
Maximum Deflection	0.03	0.03	0.02
Permanent Set	0.01	0.01	0.01
50% of Test Pressure (-52.50 psf)			
Maximum Deflection	0.03	0.03	0.03
Permanent Set	0.02	0.02	0.02
Design Pressure (-70.00 psf)			
Maximum Deflection	0.05	0.05	0.05
Permanent Set	0.02	0.02	0.02
Water Infiltration 15% Positive Design Pressure (+10.50 psf)		Pass	
Test Pressure (+105.00 psf)			
Maximum Deflection	0.06	0.06	0.05
Permanent Set	0.02	0.01	0.01
Test Pressure (-105.00 psf)			
Maximum Deflection	0.10	0.10	0.10
Permanent Set 0.02 0.02 0		0.02	
Forced Entry - ASTM F 588-07		Pass	

Note: See Architectural Testing Sketch #3 for indicator locations.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 42 of 54

31.0 Test Specimen #7 Results: (Continued)

Protocol TAS 201-94, Impact Test Procedures

Missile Weight: 9.1 lbs **Missile Length**: 94"

Muzzle Distance from Test Specimen: 16'0"

Impact #1: Missile Velocity: 49.8 fps				
Impact Area: Center of glazing				
Observations:	Missile hit target area; no rips, tears or penetrations			
Results:	Pass			

Impact #2: Missile Velocity: 49.3 fps			
Impact Area: Upper right glazing corner			
Observations:	Missile hit target area; no rips, tears or penetrations in glazing. Broke interior stop.		
Results:	Pass		

Note: See Architectural Testing Sketch #3 for impact locations.



Report Date: 02/24/12 Test Record Retention End Date: 02/16/22

Page 43 of 54



31.0 Test Specimen #7 Results: (Continued)

Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Unit #7

Design Pressure: ±70.00 psf

POSITIVE PRESSURE

Pressure Number of	Average	Maximum De	eflection at Indi	cator (inches)	
Range (psf)	Cycles	Cycle Time (seconds)	#1	#2	#3
14.0 to 35.0	3500	1.70	0.06	0.07	0.07
0 to 42.0	300	1.90	0.08	0.08	0.08
35.0 to 56.0	600	1.85	0.10	0.10	0.11
21.0 to 70.0	100	2.33	0.12	0.13	0.13
			Permanent Set (inches)		hes)
			0.06	0.06	0.07

NEGATIVE PRESSURE

Pressure Range	Number of	Average Cycle Time (seconds)	Maximum De	eflection at Indi	cator (inches)
(psf)	Cycles		#1	#2	#3
21.0 to 70.0	50	2.05	0.12	0.12	0.14
35.0 to 56.0	1050	1.32	0.10	0.09	0.11
0 to 42.0	50	2.13	0.08	0.08	0.08
14.0 to 35.0	3350	1.29	0.07	0.07	0.08
			Permanent Set (inches)		hes)
			0.01	0.01	0.01

Observations: No additional damage or deglazing was observed.

Result: Pass

Note: See Architectural Testing Sketch #3 for indicator locations.



Test Record Retention End Date: 02/16/22

Page 44 of 54

32.0 Test Specimen #8 Results: (Continued)

Protocol TAS 202-94, Static Air Pressure Tests

Test Unit #8

Architectural Testing

Design Pressure: ±70.00 psf

Title of Test	Results
Air Infiltration at 1.57 psf (25 mph)	<0.01 cfm/ft ²
Air Infiltration at 6.24 psf (50 mph)	<0.01 cfm/ft ²

	Indicator Reading (inches)		
Structural Loads 50% of Test Pressure (+52.50 psf)	#1	#2	#3
Maximum Deflection	0.01	0.01	0.01
Permanent Set	0.01	< 0.01	< 0.01
Design Pressure (+70.00 psf)			
Maximum Deflection	0.01	0.02	0.01
Permanent Set	0.01	0.01	< 0.01
50% of Test Pressure (-52.50 psf)			
Maximum Deflection	0.01	0.02	0.03
Permanent Set	0.01	0.01	0.02
Design Pressure (-70.00 psf)			
Maximum Deflection	0.02	0.03	0.03
Permanent Set	0.01	0.01	0.02
Water Infiltration 15% Positive Design Pressure (+10.50 psf)		Pass	
Test Pressure (+105.00 psf)			
Maximum Deflection	0.02	0.04	0.03
Permanent Set	0.01	< 0.01	0.01
Test Pressure (-105.00 psf)			
Maximum Deflection	0.07	0.05	0.05
Permanent Set 0.03 0.02 0.		0.02	
Forced Entry - ASTM F 588-07		Pass	

Note: See Architectural Testing Sketch #3 for indicator locations.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 45 of 54

32.0 Test Specimen #8 Results: (Continued)

Protocol TAS 201-94, Impact Test Procedures


Missile Weight: 9.1 lbs **Missile Length**: 94"

Muzzle Distance from Test Specimen: 16'0"

Impact #1: Missile Velocity: 49.1 fps				
Impact Area: Center of glazing				
Observations:	Missile hit target area; no rips, tears or penetrations			
Results:	Pass			

Impact #2: Missile Velocity: 49.6 fps			
Impact Area: Lower right glazing corner			
Observations:	Missile hit target area; no rips, tears or penetrations		
Results:	Pass		

Note: See Architectural Testing Sketch #3 for impact locations.



Test Record Retention End Date: 02/16/22

Page 46 of 54



32.0 Test Specimen #8 Results: (Continued)

Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Unit #8

Design Pressure: ±70.00 psf

POSITIVE PRESSURE

Pressure	Number of	Average Cycle Time (seconds)	Maximum Deflection at Indicator (inches)		
Range (psf)	Cycles		#1	#2	#3
14.0 to 35.0	3500	1.61	0.05	0.04	0.05
0 to 42.0	300	1.96	0.06	0.04	0.05
35.0 to 56.0	600	1.86	0.06	0.04	0.05
21.0 to 70.0	100	2.01	0.07	0.05	0.06
			Permanent Set (inches)		hes)
			0.02	0.01	0.02


NEGATIVE PRESSURE

Dango	MIIIIIII I	Average Cycle Time	Maximum De	flection at Indi	cator (inches)
(psf)	Cycles	(seconds)	#1	#2	#3
21.0 to 70.0	50	2.71	0.02	0.03	0.04
35.0 to 56.0	1050	2.06	0.01	0.03	0.03
0 to 42.0	50	2.11	0.01	0.02	0.02
14.0 to 35.0	3350	1.75	0.01	0.02	0.02
			Permanent Set (inches)		hes)
			0.01	0.02	0.02

Observations: No additional damage or deglazing was observed.

Result: Pass

Note: See Architectural Testing Sketch #3 for indicator locations. Test Specimens #8, #9 and #10 were cycled in a common chamber.



Test Record Retention End Date: 02/16/22

Page 47 of 54

33.0 Test Specimen #9 Results: (Continued)

Protocol TAS 202-94, Static Air Pressure Tests

Test Unit #9

Architectural Testing

Design Pressure: ±70.00 psf

Title of Test	Results
Air Infiltration at 1.57 psf (25 mph)	<0.01 cfm/ft ²
Air Infiltration at 6.24 psf (50 mph)	<0.01 cfm/ft ²

	Indicator Reading (inches)		
Structural Loads 50% of Test Pressure (+52.50 psf)	#1	#2	#3
Maximum Deflection	0.03	0.04	0.04
Permanent Set	0.01	0.01	0.01
Design Pressure (+70.00 psf)			
Maximum Deflection	0.03	0.04	0.04
Permanent Set	0.01	0.01	0.01
50% of Test Pressure (-52.50 psf)			
Maximum Deflection	0.01	0.02	0.02
Permanent Set	< 0.01	0.01	< 0.01
Design Pressure (-70.00 psf)			
Maximum Deflection	0.02	0.03	0.03
Permanent Set	0.01	0.01	0.01
Water Infiltration 15% Positive Design Pressure (+10.50 psf)	Pass		
Test Pressure (+105.00 psf)			
Maximum Deflection	0.03	0.05	0.05
Permanent Set	0.01	0.01	0.01
Test Pressure (-105.00 psf)			
Maximum Deflection	0.07	0.08	0.07
Permanent Set 0.01 0.01 0		0.01	
Forced Entry - ASTM F 588-07		Pass	

Note: See Architectural Testing Sketch #3 for indicator locations.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 48 of 54

33.0 Test Specimen #9 Results: (Continued)

Protocol TAS 201-94, Impact Test Procedures

Missile Weight: 9.1 lbs **Missile Length**: 94"

Muzzle Distance from Test Specimen: 16'0"

Impact #1: Missile Velocity: 49.2 fps				
Impact Area:	Center of glazing			
Observations:	Missile hit target area; no rips, tears or penetrations			
Results:	Pass			

Impact #2: Missile Velocity: 49.7 fps			
Impact Area:	Lower right glazing corner		
Observations:	Missile hit target area; no rips, tears or penetrations		
Results:	Pass		

Note: See Architectural Testing Sketch #3 for impact locations.



Report Date: 02/24/12 Test Record Retention End Date: 02/16/22

Page 49 of 54

33.0 Test Specimen #9 Results: (Continued)

Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Unit #9

Architectural Testing

Design Pressure: ±70.00 psf

POSITIVE PRESSURE

Pressure	Number of	Average Cycle Time (seconds)	Maximum De	eflection at Indi	cator (inches)
Range (psf)	Cycles		#1	#2	#3
14.0 to 35.0	3500	1.61	0.02	0.03	0.02
0 to 42.0	300	1.96	0.02	0.03	0.02
35.0 to 56.0	600	1.86	0.02	0.02	0.02
21.0 to 70.0	100	2.01	0.02	0.03	0.02
		Peri	nanent Set (inc	hes)	
			0.01	0.01	0.01

NEGATIVE PRESSURE

Pressure	Number of	Average Cycle Time	Maximum De	eflection at Indi	cator (inches)
Range (psf)	Cycles	(seconds)	#1	#2	#3
21.0 to 70.0	50	2.71	0.03	0.05	0.07
35.0 to 56.0	1050	2.06	0.03	0.05	0.06
0 to 42.0	50	2.11	0.03	0.04	0.05
14.0 to 35.0	3350	1.75	0.03	0.04	0.04
		Perr	nanent Set (inc	hes)	
			0.03	0.03	0.04

Observations: No additional damage or deglazing was observed.

Result: Pass

Note: See Architectural Testing Sketch #3 for indicator locations. Test Specimens #8, #9 and #10 were cycled in a common chamber.



Test Record Retention End Date: 02/16/22

Page 50 of 54

34.0 Test Specimen #10 Results: (Continued)

Protocol TAS 202-94, Static Air Pressure Tests

Test Unit #10

Architectural Testing

Design Pressure: ±70.00 psf

Title of Test	Results
Air Infiltration at 1.57 psf (25 mph)	<0.01 cfm/ft ²
Air Infiltration at 6.24 psf (50 mph)	<0.01 cfm/ft ²

	Indicator Reading (inches)		nches)
Structural Loads 50% of Test Pressure (+52.50 psf)	#1	#2	#3
Maximum Deflection	0.01	0.03	0.02
Permanent Set	0.01	0.01	0.01
Design Pressure (+70.00 psf)			
Maximum Deflection	0.02	0.03	0.03
Permanent Set	0.01	0.01	0.01
50% of Test Pressure (-52.50 psf)			
Maximum Deflection	0.03	0.03	0.03
Permanent Set	0.01	0.01	0.01
Design Pressure (-70.00 psf)			
Maximum Deflection	0.05	0.05	0.05
Permanent Set	0.01	0.01	0.01
Water Infiltration 15% Positive Design Pressure (+10.50 psf)	Pass		
Test Pressure (+105.00 psf)			
Maximum Deflection	0.03 0.04 0.03		0.03
Permanent Set	0.01	0.01	0.01
Test Pressure (-105.00 psf)			
Maximum Deflection	0.08 0.08 0.10		0.10
Permanent Set 0.02 0.01		0.01	0.04
Forced Entry - ASTM F 588-07		Pass	

Note: See Architectural Testing Sketch #3 for indicator locations.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 51 of 54

34.0 Test Specimen #10 Results: (Continued)

Protocol TAS 201-94, Impact Test Procedures

Missile Weight: 9.1 lbs **Missile Length**: 94"

Muzzle Distance from Test Specimen: 16'0"

Impact #1: Missile Velocity: 49.6 fps				
Impact Area:	Center of glazing			
Observations:	Missile hit target area; no rips, tears or penetrations			
Results:	Pass			

Impact #2: Missile Velocity: 49.7 fps				
Impact Area:	Lower right glazing corner			
Observations:	Missile hit target area; no rips, tears or penetrations			
Results:	Pass			

Note: See Architectural Testing Sketch #3 for impact locations.



Report Date: 02/24/12 Test Record Retention End Date: 02/16/22

Page 52 of 54



34.0 Test Specimen #10 Results: (Continued)

Protocol TAS 203-94, Cyclic Wind Pressure Loading

Test Unit #10

Design Pressure: ±70.00 psf

POSITIVE PRESSURE

Pressure	Number of	Average Cycle Time (seconds)	Maximum De	eflection at Indi	cator (inches)
Range (psf)	Cycles		#1	#2	#3
14.0 to 35.0	3500	1.61	0.03	0.04	0.02
0 to 42.0	300	1.96	0.03	0.04	0.02
35.0 to 56.0	600	1.86	0.03	0.04	0.02
21.0 to 70.0	100	2.01	0.04	0.04	0.03
		Perr	nanent Set (inc	hes)	
			0.01	0.01	0.01

NEGATIVE PRESSURE

Pressure	Number of	Average Cycle Time	Maximum De	eflection at Indi	cator (inches)
Range (psf)	Cycles	(seconds)	#1	#2	#3
21.0 to 70.0	50	2.71	0.05	0.04	0.06
35.0 to 56.0	1050	2.06	0.04	0.04	0.05
0 to 42.0	50	2.11	0.03	0.03	0.05
14.0 to 35.0	3350	1.75	0.03	0.03	0.04
		Perr	nanent Set (inc	hes)	
			0.02	0.01	0.04

Observations: No additional damage or deglazing was observed.

Result: Pass

Note: See Architectural Testing Sketch #3 for indicator locations. Test Specimens #8, #9 and #10 were cycled in a common chamber.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 53 of 54

35.0 Test Equipment:

Cannon: Constructed from steel piping utilizing compressed air to propel the missile

Missile: 2x4 Southern Pine

Timing Device: Electronic Beam Type

Cycling Mechanism: Computer controlled centrifugal blower with electronic pressure

measuring device

Deflection Measuring Device: Linear transducers and dial indicators

36.0 Laboratory Compliance Statements: The following are provided as required by the protocols for the testing reported herein.

Upon completion of testing, specimens tested for TAS 201-94 met the requirements of Section 1626 of the Florida Building Code, Building (2007).

Upon completion of testing, specimens tested for TAS 202-94 met the requirements of Section 1620 of the Florida Building Code, Building (2007).

Upon completion of testing, specimens tested for TAS 203-94 met the requirements of Section 1626 of the Florida Building Code, Building (2007).

Tape and film were not used to seal against air leakage during structural testing. In our opinion, the tape and film did not influence the results of the test.



Report Date: 02/24/12

Test Record Retention End Date: 02/16/22

Page 54 of 54

The service life of this report will expire on the stated Test Record Retention End Date, at which time such materials as drawings, data sheets, samples of test specimens, copies of this report, and any other pertinent project documentation, shall be discarded without notice.

If test specimen contains glazing, no conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimens can be made. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimens tested. This report may not be reproduced, except in full, without the written approval of Architectural Testing, Inc.

For ARCHITECTURAL TESTING, Inc.

Eric J. Schoenthaler Project Manager Shawn G. Collins, P.E. Laboratory Support Engineer

EJS:cmd/jb

Attachments (pages): This report is complete only when all attachments listed are included.

Appendix-A: Sketches (4) Appendix-B: Drawings (24)


This report produced from controlled document template ATI 00501, issued 06/10/11.




Report Date: 02/24/12 Test Record Retention End Date: 02/16/22

Appendix A

Sketches





UNIT 1

UNIT 2

 \times = INDICATOR LOCATION


X = IMPACT LOCATION


PROJECT NO.	c
B5634.01-201-18	 P

CLIENT:
KML WINDOWS, INC,
PROJECT NAME:
Coastal Aluminum Clad Direct Glazed Fixed Windows



RAWING	
IMPACT &	
INDICAT□R	LOCATIONS





UNIT 3

UNIT 4

 \times = INDICATOR LOCATION


 $^{\mathsf{X}}\bigcirc$ = IMPACT LOCATION


PROJECT NO.	T
B5634.01-201-18	ļ,

CLIENT:
KML WINDOWS, INC.
PROJECT NAME:
Coastal Aluminum Clad Direct Glazed Fixed Windows




DRAWING	
IMPACT &	
INDICAT□R	LOCATIONS





UNIT 5

UNIT 6



UNIT 7

 \times = INDICATOR LOCATION

X = IMPACT LOCATION


PROJECT NO. C

CLIENT:
KML WINDOWS, INC.
PROJECT NAME:
Coastal Aluminum Clad Direct Glazed Fixed Windows


Architectural Testing

DRAWING
IMPACT &
INDICATOR LOCATIONS


DWG. BY: PAGE
HMD 3 DH
DATE:
12/28/11 4



UNIT 8



UNIT 9



UNIT 10

 \times = INDICATOR LOCATION

 $^{\mathsf{X}}\bigcirc = \mathsf{IMPACT} \mathsf{L}\square\mathsf{CATION}$

PROJECT NO.	ľ
B5634.01-201-18	ا

CLIENT:
KML WINDOWS, INC.
PROJECT NAME:
Coastal Aluminum Clad Direct Glazed Fixed Windows




DRAWING	
IMPACT &	
INDICAT⊡R	LOCATIONS



Report Date: 02/24/12 Test Record Retention End Date: 02/16/22

Appendix B

Drawings





Title:

Specifications for Aluminium Clad Direct Glazed Windows Number: PP09KM0022

Page: 2 of 3

Issued By:

Graham Marks

Approved By: Sean Dixon

Specifications	Standard Hallmark Certified Products	Impact Certified Products (Coastal)	
Standards	AAMA/WDMA/CSA 101/I.S.2/A440-05 & 08	ASTM E1886/E1996-05 & 06 Missile Level D Wind Zone 4 and Florida Building Code HVHZ (TAS 201-94, TAS 202-94 & TAS-203-94)	
Rating	FW-LC50 125"x84" (A440-05) Class LC-PG50 125"x84" - FW (A440-08)	36" x 60" (Tested Size): +70/-70 54" x 96" (Tested Size): +70/-70 60" x 120" (Tested Size): +70/-80	
Frame Member Corner Assembly	(2 AKG)(3) # 8 x 2" screws each corner − Standard Jamb (3) #8 x 2" screws each corner − Thick Jamb (2) minimum #8 x 2" screws each corner- A Series Jamb		
Frame Member Corner Sealing	Preformed EPDM or Silicone (depends on color) two sided adhesive foam gaskets	Preformed EPDM or Silicone (depends on color) two sided adhesive foam gaskets	*************
Springline Unit Frame Member – Leg to Curved Head Assembly Butt Joint	(3) #8 x 2" P.H. (1) 24 GA – 12" Galvan	thod – Butt Joint , SQ, SMS Screw Test sample complies with these de ized Gusset Plate per Side	···g :tails
Springline Unit Frame Member – Leg to Curved Head Sealing Butt Joint	PVA Wood Glue for v	wood to wood butt joint 13:12 Tech gk	
Frame Cladding Corner Sealing	Preformed EPDM or Silicone (depends on color) two sided adhesive foam gaskets	Preformed EPDM or Silicone (depends on color) two sided adhesive foam gaskets	
Large Springline Unit with 2 pcs. Curved Frame Cladding Center Joint Sealing	Use Butyl Tape between curved center Butt Joint. Drill & Pump Dow Corning 1199 silicone sealant into both sides of frame extrusion cavity.		
Frame Cladding Assembly & Frame Cladding Corner Assembly	1/4" x 3/8" staples @ 7"(max.) from ends & 8" O.C. maximum. Also, staples on back of jamb, random as required. Dry fit no sealant Standard Jamb- (1) #8 x 1" screws & (1) #8x2 ½" Thick Jamb- (2) #8 x 1" screws A Series Jamb- (2) #8 x 2 ½" screws	1/4" x 3/8" Staples @ 7" (max.) from ends & 8" O.C. maximum. Also, staples on back of jamb, random as required. Dry fit no sealant Standard Jamb- (1) #8 x 1" screws & (1) #8x2 ½" Thick Jamb- (2) #8 x 1" screws & (1) #8 x 2 ½" A- Series Jamb- (2) #8 x 2 ½" screws	/
Glazing Method	Glass is set from interior against a bed of Dow Corning 1199 silicone sealant with a double sided adhesive foam tape and a perimeter cap bead of Dow 891 silicone sealant. Color match silicone to standard cladding color options. Wood glazing stops with double sided adhesive tape and fastened with I-1/4" staples @ 2" from ends & 8" O.C. maximum.	Glass is set from interior against a 1/8" bed of Dow Corning 995 Black Structural Silicone Sealant using glazing bumpons spacers to obtain glazing bead thickness for all color options except White 995 silicone is used for White Cladding Option. Structural Silicone is also used in the full perimeter in the Glazing Cavity. Wood Glazing Stops with double sided adhesive tape and fastened with 1-1/4" brad nails (Standard or Thick jamb) or 1 5/8" brad nails (A-Series jamb) @ 2" from ends & 6" O.C. maximum.	
Glass Options	Any Monolithic or Insulated unit that meets the size and wind-load requirements of ASTM E1300 that does not exceed product rating.	Standard Direct Glazed Units 1) Up to 36" x 60" Frame size use 5/32" AN./.090 PVB/ 5/32" AN. Laminated glass. Laminated Glass can be used as Monolithic or in an Insulated unit with 1/8" Annealed Glass.	



Title:

Specifications for Aluminium Clad Direct Glazed Windows Number: PP09KM0022

Page: 3 of 3

Issued By: Graham Marks

Approved By: Sean Dixon

Specifications	Standard Hallmark Certified Products	Impact Certified Products (Coastal)
		2) Up to 54"x96" Frame size use ¼" AN./.090 SGP/1/4" AN. Laminated glass. Laminated Glass can be used as Monolithic or in an insulated unit with ¼ "Tempered glass.
		3) Up to 60" x 120" Frame size use 1/4" HS./.090 SGP/ 1/4" HS. Laminated Glass. Laminated Glass can be use as Monolithic or in an Insulated Unit with 1/4" Tempered Glass.
		A-Series Direct Glazed Units 1) Up to 36" x 60" Frame size use 5/32" AN./.090 PVB/ 5/32" AN. Laminated glass. Laminated Glass must be used as part of an Insulated unit with 1/8" Annealed Glass.
		** Insul. Unit exterior light can also be supplied in tempered glass.
		2) Up to 54" x 96" Frame size use ¼" AN./.090 SGP/1/4" AN. Laminated glass. Laminated Glass must be used as part of an Insulated unit with 1/4" Tempered Glass.
		3) Up to 60" x 120" Frame size use 1/4" HS/.090 SGP/1/4" HS Laminated Glass. Laminated Glass mus be used as part of an Insulated unit with 1/4" Tempered Glass.
	125" x 84" maximum size.	60" x 120" maximum size.
Frame Size Restrictions	Note- Other sizes available by Comparative or Extrapolation analysis per WDMA I.S. 11.	Note- Other sizes available by Comparative or Extrapolation analysis per WDMA I.S. 11.
Frame Installation Clip Options	Standard installation clip fastened to frame with (2) #8 x ¾", FH, PD, SS screws. Clip spacing: 4" from corners and O.C. spacing as noted on the production order paperwork.	Coastal installation clip fastened to the frame with (3) #8 x ¾", FH, PD, screw. Clip spacing: 4" from corners and O.C. spacing as noted on the production order paperwork.
	Sheer Screw Option Thru Jamb - #10 x 3" @ 4" from corner and 8" minimum & 24" O.C. maximum.	Sheer screw option through jamb #12 x 2-1/2" @ 4" from corners and 6" O.C. maximum.





Test sample complies with these details. Deviations are noted.


Report# 35634


Date 113.12

Tech_Q/











Title:

Specifications for Aluminium Clad Direct Glazed Windows Number: PP09KM0022

Page: 2 of 3

Issued By: Graham Marks Approved By: Sean Dixon

Specifications	Standard Hallmark Certified Products	Impact Certified Products (Coastal)
Standards	AAMA/WDMA/CSA 101/I.S.2/A440-05 & 08	ASTM E1886/E1996-05 & 06 Missile Level D Wind Zone 4 and Florida Building Code HVHZ (TAS 201-94, TAS 202-94 & TAS-203-94)
Rating	FW-LC50 125"x84" (A440-05) Class LC-PG50 125"x84" - FW (A440-08)	36" x 60" (Tested Size): +70/-70 54" x 96" (Tested Size): +70/-70 60" x 120" (Tested Size): +70/-80
Frame Member Corner Assembly	(2 AKG)(3) # 8 x 2" screws each corner – Standard Jamb (3) #8 x 2" screws each corner – Thick Jamb (2) minimum #8 x 2" screws each corner- A Series Jamb	
Frame Member Corner Sealing	Preformed EPDM or Silicone (depends on color) two sided adhesive foam gaskets	Preformed EPDM or Silicone (depends on color) two sided adhesive foam gaskets
Springline Unit Frame Member – Leg to Curved Head Assembly Butt Joint	(3) #8 x 2" P.H. (1) 24 GA – 12" Galvan	thod – Butt Joint , SQ, SMS Screw ized Gusset Plate per Side P.D., SMS Screws
Springline Unit Frame Member – Leg to Curved Head Sealing Butt Joint		wood to wood butt joint Architectural Testing
Frame Cladding Corner Sealing	Preformed EPDM or Silicone (depends on color) two sided adhesive foam gaskets	two sided adhesive foamigaskets inted.
Large Springline Unit with 2 pcs. Curved Frame Cladding	Dilli & I think Dow Corning 1199 sincone se	Reports 55634 Curved center Buit Joint: Tech Alexandrian alant into both sides of frame extrusion cavity.
Frame Cladding Assembly & Frame Cladding Corner Assembly	1/4" x 3/8" staples @ 7"(max.) from ends & 8" O.C. maximum. Also, staples on back of jamb, random as required. Dry fit no sealant Standard Jamb- (1) #8 x 1" screws & (1) #8x2 ½" Thick Jamb- (2) #8 x 1" screws A Series Jamb- (2) #8 x 2 ½" screws	1/4" x 3/8" Staples @ 7" (max.) from ends & 8" O.C. maximum. Also, staples on back of jamb, random as required. Dry fit no sealant Standard Jamb- (1) #8 x 1" screws & (1) #8x2 ½" Thick Jamb- (2) #8 x 1" screws & (1) #8 x 2 ½" A- Series Jamb- (2) #8 x 2 ½" screws
Glazing Method	Glass is set from interior against a bed of Dow Corning 1199 silicone sealant with a double sided adhesive foam tape and a perimeter cap bead of Dow 891 silicone sealant. Color match silicone to standard cladding color options. Wood glazing stops with double sided adhesive tape and fastened with 1-1/4" staples @ 2" from ends & 8" O.C. maximum.	jamb) or 1 5/8" brad nails (A-Series jamb) @ 2" from ends & 6" O.C. maximum.
Glass Options	Any Monolithic or Insulated unit that meets the size and wind-load requirements of ASTM E1300 that does not exceed product rating.	Standard Direct Glazed Units 1) Up to 36" x 60" Frame size use 5/32" AN./.090 PVB/ 5/32" AN. Laminated glass. Laminated Glass can be used as Monolithic or in an Insulated unit with 1/8" Annealed Glass.



Title:

Specifications for Aluminium Clad Direct Glazed Windows Number: PP09KM0022 Page: 3 of 3

Issued By:

Graham Marks

Approved By: Sean Dixon

Specifications	Standard Hallmark Certified Products	Impact Certified Products (Coastal)
		2) Up to 54"x96" Frame size use ¼" AN./.090 SGP/1/4" AN. Laminated glass. Laminated Glass can be used as Monolithic or in an insulated unit with ¼ "Tempered glass.
		3) Up to 60" x 120" Frame size use 1/4" HS./.090 SGP/ 1/4" HS. Laminated Glass. Laminated Glass can be use as Monolithic or in an Insulated Unit with 1/4" Tempered Glass.
		A-Series Direct Glazed Units 1) Up to 36" x 60" Frame size use 5/32" AN./.090 PVB/ 5/32" AN. Laminated glass. Laminated Glass must be used as part of an Insulated unit with 1/8" Annealed Glass.
		** Insul. Unit exterior light can also be supplied in tempered glass.
		2) Up to 54" x 96" Frame size use ¼" AN /.090 SGP/1/4" AN. Laminated glass. Laminated Glass must be used as part of an Insulated unit with 1/4" Tempered Glass.
		3) Up to 60" x 120" Frame size use 1/4" HS/.090 SGP/1/4" HS Laminated Glass. Laminated Glass must be used as part of an Insulated unit with 1/4" Tempered Glass.
	125" x 84" maximum size.	60" x 120" maximum size.
Frame Size Restrictions	Note- Other sizes available by Comparative or Extrapolation analysis per WDMA I.S. 11.	Note- Other sizes available by Comparative or Extrapolation analysis per WDMA I.S. 11.
Frame Installation Clip Options	Standard installation clip fastened to frame with (2) #8 x 3/4", FH, PD, SS screws. Clip spacing: 4" from corners and O.C. spacing as noted on the production order paperwork.	Coastal installation clip fastened to the frame with (3) #8 x ¾", FH, PD, screw. Clip spacing: 4" from corners and O.C. spacing as noted on the production order paperwork.
	Sheer Screw Option Thru Jamb - #10 x 3" @ 4" from corner and 8" minimum & 24" O.C. maximum.	Sheer screw option through jamb #12 x 2-1/2" @ 4" from corners and 6" O.C. maximum.



Architectural Testing


Test sample complies with these details.


Deviations are noted.


Report# 35634


Date 1:13:12


Tech A



















Process Specification

Title:

Specifications for Aluminium Clad Direct Glazed Windows Number: PP09KM0022

Page: 2 of 3

Issued By: Graham Marks

Approved By: Sean Dixon

Specifications	Standard Hallmark Certified Products	Impact Certified Products (Coastal)
Standards	AAMA/WDMA/CSA 101/I.S.2/A440-05 & 08	ASTM E1886/E1996-05 & 06 Missile Level D Wind Zone 4 and Florida Building Code HVHZ (TAS 201-94, TAS 202-94 & TAS-203-94)
Rating	FW-LC50 125"x84" (A440-05) Class LC-PG50 125"x84" - FW (A440-08)	36" x 60" (Tested Size): +70/-70 54" x 96" (Tested Size): +70/-70 60" x 120" (Tested Size): +70/-80
Frame Member Corner Assembly	(2 AKG)(3) # 8 x 2" screws each corner – Standard Jamb (3) #8 x 2" screws each corner – Thick Jamb (2) minimum #8 x 2" screws each corner- A Series Jamb	
Frame Member Corner Sealing	Preformed EPDM or Silicone (depends on color) two sided adhesive foam gaskets	Preformed EPDM or Silicone (depends on color) two sided adhesive foam gaskets
Springline Unit Frame Member – Leg to Curved Head Assembly Butt Joint	(3) #8 x 2" P.H. (1) 24 GA – 12" Galvani	thod – Butt Joint , SQ, SMS Screw ized Gusset Plate per Side , P.D., SMS Screws Test sample complies with the se
Springline Unit Frame Member – Leg to Curved Head Sealing Butt Joint	PVA Wood Glue for v	Deviations are noted. wood to wood butt joinport: 85634 Oste 1:13:12 Tech 9
Frame Cladding Corner Sealing	Preformed EPDM or Silicone (depends on color) two sided adhesive foam gaskets	Preformed EPDM or Silicone (depends on color) two sided adhesive foam gaskets
Large Springline Unit with 2 pcs. Curved Frame Cladding Center Joint Sealing	Use Butyl Tape between curved center Butt Joint. Drill & Pump Dow Corning 1199 silicone sealant into both sides of frame extrusion cavity.	
Frame Cladding Assembly & Frame Cladding Corner Assembly	1/4" x 3/8" staples @ 7"(max.) from ends & 8" O.C. maximum. Also, staples on back of jamb, random as required. Dry fit no sealant Standard Jamb- (1) #8 x 1" screws & (1) #8x2 ½" Thick Jamb- (2) #8 x 1" screws A Series Jamb- (2) #8 x 2 ½" screws	1/4" x 3/8" Staples @ 7" (max.) from ends & 8" O.C. maximum. Also, staples on back of jamb, random as required. Dry fit no sealant Standard Jamb- (1) #8 x 1" screws & (1) #8x2 ½" Thick Jamb- (2) #8 x 1" screws & (1) #8 x 2 ½" A- Series Jamb- (2) #8 x 2 ½" screws
Glazing Method	Glass is set from interior against a bed of Dow Corning 1199 silicone sealant with a double sided adhesive foam tape and a perimeter cap bead of Dow 891 silicone sealant. Color match silicone to standard cladding color options. Wood glazing stops with double sided adhesive tape and fastened with 1-1/4" staples @ 2" from ends & 8" O.C. maximum.	Glass is set from interior against a 1/8" bed of Dow Corning 995 Black Structural Silicone Sealant using glazing bumpons spacers to obtain glazing bead thickness for all color options except White 995 silicone is used for White Cladding Option. Structural Silicone is also used in the full perimeter in the Glazing Cavity. Wood Glazing Stops with double sided adhesive tape and fastened with 1-1/4" brad nails (Standard or Thick jamb) or 1 5/8" brad nails (A-Series jamb) @ 2" from ends & 6" O.C. maximum.
Glass Options	Any Monolithic or Insulated unit that meets the size and wind-load requirements of ASTM E1300 that does not exceed product rating.	Standard Direct Glazed Units 1) Up to 36" x 60" Frame size use 5/32" AN /.090 PVB/ 5/32" AN. Laminated glass. Laminated Glass can be used as Monolithic or in an Insulated unit with 1/8" Annealed Glass.



Process Specification

Title:

Specifications for Aluminium Clad Direct Glazed Windows Number: PP09KM0022

Page: 3 of 3

Issued By:

Graham Marks

Approved By: Sean Dixon

Specifications	Standard Hallmark Certified Products	Impact Certified Products (Coastal)
		2) Up to 54"x96" Frame size use ¼" AN./.090 SGP/1/4" AN. Laminated glass. Laminated Glass can be used as Monolithic or in an insulated unit with ¼ " Tempered glass.
		3) Up to 60" x 120" Frame size use 1/4" HS./.090 SGP/ 1/4" HS. Laminated Glass. Laminated Glass can be use as Monolithic or in an Insulated Unit with 1/4" Tempered Glass.
		A-Series Direct Glazed Units 1) Up to 36" x 60" Frame size use 5/32" AN./.090 PVB/ 5/32" AN. Laminated glass. Laminated Glass must be used as part of an Insulated unit with 1/8" Annealed Glass.
		** Insul. Unit exterior light can also be supplied in tempered glass.
:		2) Up to 54" x 96" Frame size use ¼" AN./.090 SGP/1/4" AN. Laminated glass. Laminated Glass must be used as part of an Insulated unit with 1/4" Tempered Glass.
		3) Up to 60" x 120" Frame size use 1/4" HS/.090 SGP/1/4" HS Laminated Glass. Laminated Glass must be used as part of an Insulated unit with 1/4" Tempered Glass.
TE C'	125" x 84" maximum size.	60" x 120" maximum size.
Frame Size Restrictions	Note- Other sizes available by Comparative or Extrapolation analysis per WDMA I.S. 11.	Note- Other sizes available by Comparative or Extrapolation analysis per WDMA I.S. 11.
Frame Installation Clip Options	Standard installation clip fastened to frame with (2) #8 x ¾", FH, PD, SS screws. Clip spacing: 4" from corners and O.C. spacing as noted on the production order paperwork.	Coastal installation clip fastened to the frame with (3) #8 x ¾", FH, PD, screw. Clip spacing: 4" from corners and O.C. spacing as noted on the production order paperwork.
	Sheer Screw Option Thru Jamb - #10 x 3" @ 4" from corner and 8" minimum & 24" O.C. maximum.	Sheer screw option through jamb #12 x 2-1/2" @ 4" v from corners and 6" O.C. maximum.



Architectural Testing

Test sample complies with these details. Deviations are noted.

Report# <u>85634</u>

Date 1.13.12

Tech (

